Straviwood WallBreak-P
Installation Manual

straviwood
by CDM Stravitec

Installation Tools and Components

- Ink marker
- Pocket tape measure
- Clean cloth
- Personal protective equipment (PPE)

1 / Supporting Floor & System Components

Ensure the supporting floor is physically sound, clean and dry prior to installation. Mark where the Straviwood WallBreak-P bearings will be installed and apply a thin layer of glue in a zig-zag pattern.

Recommended Glue

- Rectavit S40 Flex MS Polymer
- Rectavit 1129 Fat Forward
- Rectavit 1128 EPDM Spray
- Rectavit G60 Pro Heavy Duty

2 / Install Straviwood WallBreak-P Bearings

Place the Straviwood WallBreak-P bearings on top of the glue and press firmly in order to reduce the thickness of the glue to a minimum.

Remove any access glue coming out from under the pads with a clean cloth.

3 / Install The Wall

After installing the Straviwood WallBreak-P bearings, the CLT-walls can be placed on top of the pads. Be careful not to damage the pads while installing the walls.

Alternatively, the Straviwood WallBreak-P bearings can be installed on the CLT-walls in factory.

DISCLAIMER

This information is accurate to the best of our knowledge at the time of issue. Information, data and recommendations provided are based on industry accepted testing and prior product usage. It is intended as descriptive of the general capabilities and performance of our products and does not endorse applicability for any particular project. We reserve the right to change products, performance, and data without notice. This document replaces all information supplied prior to the publication hereof.

REUTENBEEK 9-11, 3090 OVERIJSE, BELGIUM
T +32 2 687 79 07 / F +32 2 687 35 52 / INFO@CDM-STRAVITEC.COM / WWW.CDM-STRAVITEC.COM

INSTALLATION MANUAL STRAVIWOOD WALLBREAK-P / 1